#### **GENERAL NOTES:**

1. Source of Topography. 2005 SURVEY BY BRELJIE AND RACE 5570 Skylane Blvd. Santa Rosa, CA 95403. 2. Datums:

HORIZONTAL: ASSUMED

**VERTICAL: ASSUMED** 

3. Design Intent. These drawings represent the general design intent to be implemented and contractor is responsible for all items shown on these Plans. Contractor shall be responsible for contacting Engineer for any clarifications or further details necessary to accommodate actual site conditions. Any deviation from these plans without the Engineers approval are at the Contractor's own risk and expense. Notify Engineer immediately of any unexpected and changed conditions, safety hazards, and environmental problems encountered.

4. Pre-construction Meeting. A Pre-construction meeting will be held at the job site(s) to be attended by the the Engineer and the Construction site foreman and key contractor work personnel. The purpose of the meeting is to go over the work, provide clarifications, and discuss conditions of the permits. Special attention will be paid to Fisheries and Endangered Species issues and protection requirements. Provide Engineer with minimum 72 hours notice prior to meeting. Notice to proceed will be provided at completion of Pre-construction meeting.

5. Completion Schedule. Provide Engineer with project construction completion schedule within 72 hours of award of contract. All work within stream channels must be completed by October 15, 2009 and all erosion control measures must be in place by October 15, 2009. All contract work must be completed and contractor demobilized by November 15, 2009.

6. Clarifications, Change Orders, and Additional Work . The Engineer, acting on behalf of the Camp Meeker Recreation & Park District, may require revisions in the Plans due to unforseen circumstances and problems that may arise in the field. Extra Work will be that as defined in State of California Caltrans Standard Specifications. Contractor is to promptly notify the City's Project Manager of all work considered Extra. Written cost estimates will be required for all Extra Work and written change orders will be executed upon the recommendation of the Engineer by the Gold Ridge RCD.

7. Materials and Workmanship. All materials, workmanship, and construction shall conform to State of California CalTrans Standard Plans and Specifications unless

8. Job Site Conditions and Contractor Responsibility . Contractor shall assume sole and complete responsibility for site conditions during the course of the construction of this project, including the safety of all persons and property, and all environmental protection elements, whether shown on these Drawings or not. Contractor shall follow all applicable construction and safety regulations. These requirement shall apply continuously and will not be limited to normal working hours. The Contractor shall defend, indemnify, and hold Camp Meeker, Gold Ridge RCD and the project engineer (Questa Engineering Corporation) harmless from any and all liability, real or alleged, in connection with the performance of work on this project, except from liability arising from the sole negligence of the Owner or Engineer.

9. Damage. Contractor shall exercise care to avoid damage to existing public and private property, including ornamental and native trees and shrubs, and other property improvements. If contractor causes damages to such items, he shall be responsible for repair or replacement in like number, kind, condition, and size. Any such cost may be deducted by RCD from monies due Contractor under this contract.

10. Limits of Work, Access, Staging and Mobilization Areas . The approximate Limits of Work are shown on the Drawings. Exact Limits of Work, points of ingress-egress, creek channel access, mobilization, staging, and work areas will be flagged in the field by the Project Manager or Engineer. All materials, excess soil, demolition debris and rubble, and equipment storage must occur within the staging and mobilization area. Equipment maintenance and fueling must occur within the staging and mobilization areas.

11. Utilities. Prior to commencing construction, the Contractor is required to contact the utility companies involved and request a visual verification of the location of their underground facilities. It shall be the responsibility of the contractor to identify, locate, and protect all underground utilities. The utility companies are thought to be members of the Underground Service Alert (U.S.A.) On-call program. The contractor shall notify the USA 48 hours in advance of performing excavation work by calling toll-free 1-800-642-2444.

12. Erosion Control. Contractor is responsible for all erosion control as part of the work.

Install silt fence and/or hay bale barrier at downslope end of all channel grading projects prior to initiation of creek grading work. Hydroseed or broadcast seed, rake and straw mulch all disturbed areas upon job completion as shown on Drawings.

13. Work in Stream Channels and Stream Diversions . All work involving use of heavy equipment must be completed from top of bank unless a specific point of creek channel access has been approved and is shown on the plans, and then only in non-live water as defined by the Calif. Dept. of Fish and Game. The Contractor shall be responsible for following the Stream Diversion and Water Control Plan. All stream diversion and water control work is assumed to be a part of the mobilization and/or earthwork job requirements for payment purposes.

At or before the Pre-construction meeting the Contractor shall submit written and/or graphic descriptions of how the project site work areas will be dewatered, including but not limited to bypassing low flows around the work site to a point downstream of a silt trap (if deemed necessary), constructing of such a silt trap, necessary holding facilities, upstream or downstream cofferdams, pumps, or pipe conveyance systems. In general sand bag and geotextile filter fabric diversion structures and creek lining are preferred. Contractor is responsible for removal and disposition of all water control structures.

The Contractor shall furnish, install, and operate all necessary machinery, appliances, and equipment to divert flowing water around work areas, and to keep excavations and trenches reasonably free from water during construction. Contractor shall dispose of the water so as not to cause injury to public or private property, or to cause a nuisance or a menace to the public, or to degrade water quality. He shall at all times have on hand sufficient pumping equipment and machinery in good working condition for all ordinary emergencies and shall have available at all times competent mechanics for the operation of all pumping equipment. If the Contractor chooses to use a pumping system for any portion of the water control work, he shall have adequate back-up equipment to insure the continuous operation of the equipment.

The Contractor shall at all times provide for the adequate return flow of diversions below the project site. The Contractor may temporarily divert water during construction, as outlined in their approved Stream Diversion and Water Control Plan. This may include for instance, visqueen and straw bale or sand bag diversion dikes and piping systems.

Turbid dewatering flows shall be pumped into a holding facility or sprayed over a large area outside the stream channel to allow for natural filtration of sediments. At no time shall turbid water be allowed back into the stream channel until water is clear of silt.

All heavy equipment must have a supply of sorbent pads available to clean-up grease, oil, or fuel that drips or spills into the stream channel. Sorbent booms must be placed downstream from locations where machinery is expected to cross the stream channel. Used pads and booms are to be disposed of properly at Contractor's

14. Endangered species may be present in the work areas . The regulatory agencies including the California Dept. of Fish and Game, the U.S. Fish and Wildlife Service, and the National Marine Fisheries Service will issue terms and conditions and other permit requirements related to work in or near the stream channel. This will likely require periodic inspections, monitoring, and capturing and moving fish and other aquatic organisms. Camp Meeker will be responsible for providing a Biological Monitor to perform the required inspections, monitoring, and capture and move work tasks. Contractor is to coordinate with Engineer and Biologist in meeting these conditions of approval. The Biologist will have the authority to shut down the job site if in their opinion, Contractor is violating conditions of the permits, or if there is a significant threat to the safety of the Endangered Species.

15. Earthwork and Grading. All earthwork and grading shall be done in conformance with Chapter 33 of the UBC, the Grading Ordinance of Sonoma County, and as shown on these Drawings. Grading work will be completed under the direct supervision of the Engineer. Contractor is to provide a smooth or uniform slope as shown on the Drawings, and uniform transition to adjacent natural grades. Clearing for earthwork and grading shall be narrowly confined to only that absolutely necessary to complete the work, within the Limits of Work. Additional, unauthorized grading outside of the Limits of Work will not be compensated for, and must be restored and repaired by Contractor. The final grade must be approved by Engineer.

**16. Earthwork Quantities** . Contractor is responsible for all earthwork, including grading, provision and placement of rock meeting size limits, as shown on Drawings, and off-haul and legal disposal of all excess soil and rubble. Earthwork quantities, including grading, placed rock rip-rap and off-haul quantity estimates provided by Engineer is for purposes of estimating permit fees and for bid comparison only. Contractor is responsible for pre-bid job site inspection and independent estimation of all quantities. City and Engineer do not, expressly or otherwise by implication, extend any warranty to earthwork calculations.

17. Archaeological Resources. If Archaeological or Cultural Resources are identified during the work, then all work will halt in the affected area until a qualified professional is brought in to determine the significance of the resources, assess the situation and make recommendations.

The Owner will be responsible for developing and implementing a plan for dealing with the resources.

Sec. 404 permit issued by US Army Corps of Engineers

1602/1603 Streambed Alteration Agreement issued by CA Dept. Fish & Game NPDES Storm Water Discharge permit and Water Quality Certification, by North Coast Regional Water Quality Control Board US Fish and Wildlife Service Consultation and Implementation Recommendations

National Marine Fisheries Service Consultation and Implementation Recommendations

The Contractor shall be given copies of all the permits, shall become familiar with the permit requirements, and shall be responsible for adherence to and conformance with all permit conditions as part of the overall work, including possible fines and mitigation for violations. No additional charges will be allowed for permit compliance work.

#### 18. Telephone Numbers.

Client: Gold Ridge RCD Contact: Lisa Hulette (707) 874-2907

Consultant: Questa Engineering Corporation


Contact: Syd Temple (510) 236-6114



REGIONAL VICINITY

# SHEET LEGEND:

- TITLE SHEET
- STAGING AND SURVEY CONTROL PLAN
- DEMOLITION AND DEWATERING PLAN
- GRADING PLAN AND PROFILE
- IMPROVEMENTS PLAN
- **CROSS SECTIONS & PROFILE**
- STORMDRAIN AND STAIRWAY DETAILS
- BANK AND CHANNEL STABILIZATION DETAILS
- PLANTING & EROSION CONTROL PLAN
- STRUCTURAL GENERAL PLAN
- STRUCTURAL FOUNDATION PLAN
- STRUCTURAL ABUTMENT 1 LAYOUT
- STRUCTURAL ABUTMENT 2 LAYOUT
- STRUCTURAL ABUTMENT DETAILS
- STRUCTURAL MISCELLANEOUS DETAILS



**PROJECT VICINITY** 

DUTCH BILL CREEK DAM REMOVAL CAMP MEEKER PARKS AND RECREATION CAMP MEEKER, CALIFORNIA







Sht:	Rev:	Date:	Ву:	Description: A	.pp'd:	Design:	<u> С</u> Т
							S.T.
						Drawn:	W.S./M.L.
						Checked:	
							S.T
					J	Appr'd:	ST

TITLE SHEET

**DUTCH BILL CREEK** CAMP MEEKER, CALIFORNIA Size Project No. D 250041 AS SHOWN 6/05/09 of **15** 






CAMP MEEKER, CALIFORNIA



REGISTAN	PROFESSION ONEY A. TEN	
A	12-30-09 EXPIRES  OF CALLED	∴ Add

Sht:	Rev:	Date:	Ву:	Description:	App'd:	Design:
						Design: S.T./R.A.B.
						Drawn: W.S./M.L.
						Checked:
						S.T.
						Appr'd: S.T.





ENGINEERING CORP. P.O. Box 70356 1220 Brickyard Cove Road Point Richmond, CA 94807





Sht:	Rev:	Date:	Ву:	Description: A	pp'd:	Design: S.T./R.A.B.
						Drawn:
						W.S./M.L.
						Checked:
						Appr'd:
					J	$\int_{0}^{\infty} S.T.$


CAMP MEEKER, CALIFORNIA
























DUTCH BILL CREEK DAM REMOVAL

CAMP MEEKER PARKS AND RECREATION

CAMP MEEKER, CALIFORNIA





Sht:	Rev:	Date:	Ву:	Description: App'd:	Design:	T./R.A.B.
					Drawn:	W.S./M.L.
					Checked:	VV.3./IVI.L.
					Appr'd:	<u>S.1.</u>
					лррі ц.	S.T.

BANK AND CHANNEL STABILIZATION DETAILS

ABILIZATION DETAILS

DUTCH BILL CREEK

CAMP MEEKER, CALIFORNIA

Scale:

AS

Date:


Sheet: S


Size Project No. D 250041


Scale: AS SHOWN


Date: 6/05/09

Sheet: 8 OF 15









#### CONCRETE STRENGTH AND TYPE LIMITS NO SCALE:

#### LEGEND:

STRUCTURAL CONCRETE, BRIDGE (3600 PSI @ 28 DAYS)

24" CIDH PILE (3600 PSI @ 28 DAYS)

#### GENERAL NOTES

DESIGN 2001 CALIFORNIA BUILDING CODE (CBC)

CALTRANS SEISMIC DESIGN CRITERIA (SDC) VERSION 1.4, DATED JUNE 2006 SEISMIC DESIGN

DEAD LOAD 26.60 KIP PER ABUTMENT UNIFORM LIVE LOAD 25.50 KIP PER ABUTMENT 8.00 KIP PER ABUTMENT VEHICLE LOAD

REINFORCED fy = 60,000 PSI

CONCRETE f'c = 3,600 PSI, UNLESS OTHER SPECIFIED

n = 8.5

#### HYDROLOGIC SUMMARY

DRAINAGE AREA: 2.80 SQUARE MILES

DESIGN FLOOD BASE OVERTAPPING FLOOD FLOOD FREQUENCY (YRS) 100 N/A DISCHARGE (CFT/SEC) 2,710 N/A WATER SURFACE 967.00 N/A

FLOOD PLAIN DATA ARE BASED UPON INFORMATION AVAILABLE WHEN THE PLANS WERE PREPARED AND SHOWN TO MEET FEDERAL REQUIREMENTS. THE ACCURACY OF SAID INFORMATION IS NOT WARRANTED BY THE STATE AND INTERESTED OR AFFECTED PARTIES SHOULD MAKE THEIR OWN INVESTIGATION

#### LEGEND:

966.00 INDICATES BOTTOM OF ABUT FOOTING ELEVATION

#### **BENCHMARK:**

CONTROLLING POINT	NORTHING	EASTING	ELEVATION
CP-#100	9931.28	9972.91	TBO
CP-#101	10072.35	9708.21	TBO
CP-#102	10032.50	9780.68	956.50

#### NOTES:

FOR UNDERGROUND UTILITIES, SEE ROAD PLANS FOR HORIZONTAL ALIGNMENT, SEE ROAD PLANS.

CONTRACTOR TO VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DUTCH BILL CREEK DAM REMOVAL CAMP MEEKER PARKS AND RECREATION CAMP MEEKER, CALIFORNIA




SUITE 125 FOLSOM, CA 95630 (916) 294-0875 (FAX)


MAJDI M. KANAAN
No. 50238

400 PLAZA DRIVE


Sht:	Rev:	Date:	Ву:	Description:	App'd:	Design:
						M. KANA
						Drawn:
						M. KENDA
						Checked:
						A. MALLA
						Appr'd:

FOUNDATION PLAN STRUCTURAL PLANS DUTCH BILL CREEK CAMP MEEKER, CALIFORNIA






<u>ABUTMENT 1 PLAN</u> SCALE:  $\frac{3}{4}$ "=1'-0"




#### ABUTMENT 1 ELVATION SCALE: $\frac{3}{4}$ "=1'-0"



### ABUTMENT 1 FOOTING PLAN

SCALE:  $\frac{3}{4}$ "=1'-0"



ABUTMENT 1 SECTION SCALE:  $\frac{3}{4}$ "=1'-0"

1. FOR "SECTION A-A" AND "SECTION B-B" SEE "ABUTMENT DETAILS" SHEET.

CONTRACTOR TO VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DUTCH BILL CREEK DAM REMOVAL CAMP MEEKER PARKS AND RECREATION CAMP MEEKER, CALIFORNIA




400 PLAZA DRIVE SUITE 125 FOLSOM, CA 95630 (916) 294-0059 (916) 294-0875 (FAX)





Sht	Rev:	Date:	Ву:	Description:	App'd:	Design:	NA IZANIAANI
						Drawn:	M. KANAAN
							M. KENDALL
-						Checked:	A. MALLA
					<del>                                     </del>	Appr'd:	

ABUTMENT 1 LAYOUT STRUCTURAL PLANS DUTCH BILL CREEK CAMP MEEKER, CALIFORNIA

Size	Project No.	Rev
D	250041	
Scale:	AS SHOW	N
Date:	6/05/09	
Sheet	12 of 15	)









ABUTMENT 2 ELVATION

SCALE: 3/4"=1'-0"



# ABUTMENT 2 FOOTING PLAN

SCALE:  $\frac{3}{4}$ "=1'-0"



ABUTMENT 2 SECTION

SCALE: 3/4"=1'-0"

1. FOR "SECTION A-A" AND "SECTION B-B" SEE "ABUTMENT DETAILS" SHEET.

CONTRACTOR TO VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DUTCH BILL CREEK DAM REMOVAL
CAMP MEEKER PARKS AND RECREATION
CAMP MEEKER, CALIFORNIA



400 PLAZA DRIVE SUITE 125 FOLSOM, CA 95630 (916) 294-0059 (916) 294-0875 (FAX)




Sht: Rev	Date:	By:	Description:	App'd: Design: M. KAN
				Drawn:
				Checked:
				A. MAL
				Appr'd:

ABUTMENT 2 LAYOUT
STRUCTURAL PLANS


DUTCH BILL CREEK
CAMP MEEKER, CALIFORNIA

Size	Project No.	Rev.
D	250041	
Scale:	AS SHOW	N
Date:	6/05/09	
Sheet	13 of 15	)




SECTION A-A REINFORCEMENT

SCALE: 3/4"=1'-0"



SECTION B-B REINFORCEMENT

SCALE: 3/4"=1'-0"



WINGWALL REINFORCEMENT


SCALE: 3/4"=1'-0"

SECTION C-C

SCALE: 3/4"=1'-0"

CONTRACTOR TO VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DUTCH BILL CREEK DAM REMOVAL
CAMP MEEKER PARKS AND RECREATION
CAMP MEEKER, CALIFORNIA




400 PLAZA DRIVE SUITE 125 FOLSOM, CA 95630 (916) 294-0059 (916) 294-0875 (FAX)




Sht:	Rev:	Date:	Ву:	Description:	pp'd: Desigr	า:
					II	M. KANAAN
					——    Drawn	ı: M. KENDALL
					Check	
						A. MALLA
					——    Appr'c	<b>1</b> :


ABUTMENT DETAILS
STRUCTURAL PLANS
DUTCH BILL CREEK
CAMP MEEKER, CALIFORNIA

Size | Project No. | Rev. | 250041 | Scale: | AS SHOWN | Date: | 6/05/09 | Sheet: | 14 OF 15





\* EXTEND AT 2" PITCH TO TOP OF





BEARING PLATE DETAIL SCALE: 3"=1'-0"






- FILTER FABRIC WRAP AROUND

DRAIN

THE GEOCOMPOSITE

SCALE: NTS



1'-0"

– CAP TYP SEE NOTE 2

3"Ø SLOTTED PLASTIC PIPE.

SEE NOTE 2

TEE CONNECTION

— GRANULAR BACKFILL

BASE

DETAIL Y DETAIL X SCALE: NTS SCALE: NTS ALTERNATIVE TO PERVIOUS BACKFILL WEEP HOLE AND GEOCOMPOSITE DRAIN

BACKFACE OF -

ABUTMENT/WING WALL

#### <u>NOTES</u>

- 1. 4"ø DRAINS AT 13' CENTER TO CENTER, EXPOSED WALL DRAINS SHALL BE 9"± ABOVE FG.
- 2. GEOCOMPOSITE DRAIN, GRANULAR BACKFILL BASE, AND 3"Ø SLOTTED PLASTIC PIPE CONTINUOUS BEHIND ABUTMENTS AND WING WALLS, CAP ENDS OF PIPE. PROVIDE TEE CONNECTION AT EACH 4" DRAIN.
- 3. CONNECT THE LOW END OF PLASTIC PIPE TO THE MAIN OUTLET PIPE AS APPLICABLE

CONTRACTOR TO VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING ANY MATERIAL.

DUTCH BILL CREEK DAM REMOVAL CAMP MEEKER PARKS AND RECREATION CAMP MEEKER, CALIFORNIA



400 PLAZA DRIVE SUITE 125 FOLSOM, CA 95630 (916) 294-0059 (916) 294-0875 (FAX)



Sht:	Rev:	Date:	By:	Description:	App'd:	Drawn: Checked:	M. KANAAN  M. KENDALL  A. MALLA	
						Appr'd:		$\mathbb{I}$

## MISCELLANEOUS DETAILS STRUCTURAL PLANS DUTCH BILL CREEK

CAMP MEEKER, CALIFORNIA

Size Project No.
D 250041 **AS SHOWN** 6/05/09 Sheet: 15 OF 15